

# **SVLTR2800D SERIES**

# SPACE QUALIFIED HYBRID DC-DC CONVERTERS



SVLTR - Exact marking may differ from that shown

## 1.0 DESCRIPTION

The SVLTR Series of space qualified DC-DC Converters is specifically designed for the harsh radiation environment of space applications. Performance is guaranteed through the use of hardened semiconductor components, radiation lot acceptance testing (RLAT) of non-hardened components, and analysis. The SVLTR Series has been characterized for Total lonizing Dose (TID) performance including Enhanced Low Dose Rate Sensitivity (ELDRS) and for Single Event Effects (SEE) according to VPT's DLA-approved Radiation Hardness Assurance (RHA) plan per MIL-PRF-38534, Appendix G, Level L. Characterization is performed at both the component level and at the SVLTR Series hybrid converter level.

Radiation-hardened to TID levels of 60 krad(Si) and SEE to 85 MeV/mg/cm², the SVLTR Series of DC-DC Converters is suited for use in many low Earth orbit (LEO), medium Earth orbit (MEO), geostationary orbit (GEO), deep space, and launch vehicle programs.

## 1.1 FEATURES

- Up to 40 W output power
- Wide input voltage range: 15 to 50 V continuous, 80 V transient
- Continuous operation over full military temperature range of -55 °C to +125 °C with no power derating
- Very low output noise
- Radiation immune magnetic feedback circuit
- No use of optoisolators
- Undervoltage lockout
- Output overload and short circuit protection

### **Product Overview**

Input Range:	15 to 50 V continuous, 80 V transient				
Output Options:	±5 V	±12 V	±15 V		
	30 W	40 W	40 W		
MIL-PRF-38534:	Class H or Class K; RHA level L				

## 1.2 SPACE LEVEL CHARACTERIZATIONS

- Guaranteed TID performance to 60 krad(Si) including ELDRS
- SEE performance to 85 MeV/mg/cm<sup>2</sup>. Transients are fully characterized for cross section and magnitude
- Worst-case analysis, stress, radiation, reliability reports available

#### 1.3 MANUFACTURING AND COMPLIANCE

- Qualified to MIL-PRF-38534 Class H and Class K, DLA SMD # 5962-16215
- MIL-PRF-38534 element evaluated components
- MIL-STD-461 C/D/E/F when used with appropriate VPT EMI filter
- Manufactured in a MIL-PRF-38534 Class H and Class K facility
- MIL-STD-883
- ISO-9001

## 1.4 PACKAGING

- Low-profile: 2.890" x 1.125" x 0.405"
- Max weight: 55 g (flanged package)
- Industry standard pinout
- Precision seam-welded hermetic metal case
- Flanged and Non-flanged versions available

## 1.5 SIMILAR PRODUCTS AND ACCESSORIES

- SVTR 40 W space qualified dc-dc converter (30 krad, 44 MeV)
- SVRTR 40 W space qualified dc-dc converter (100 krad, 85 MeV)
- Custom versions available
- EMI filters
- Non-isolated, space qualified point of load converters
- Use with Thermal Pad TP-003

**Sales Information** Phone: (425) 353-3010 Fax: (425) 353-4030 SVLTR2800D - 2.0


Web: www.vptpower.com

E-mail: vptsales@vptpower.com




## 2.0 DIAGRAMS

## 2.1 BLOCK DIAGRAM



## 2.2 CONNECTION DIAGRAM



## 3.0 SPECIFICATIONS

# 3.1 ABSOLUTE MAXIMUM RATINGS

Absolute Maximum Ratings			
Input Voltage (Continuous):	-0.5 V to 50 V	Operating Temperature (Full Load):	-55 °C to +125 °C
Input Voltage (Transient, 1 second):	-0.5 V to 80 V	Storage Temperature:	-65 °C to +150 °C
ESD Rating per MIL-PRF-38534:	3B	Lead Solder Temperature (10 seconds):	270 °C

SVLTR2800D - 2.0 **Sales Information** Phone:(425) 353-3010 Fax: (425) 353-4030 Web: www.vptpower.com Page 2

E-mail: vptsales@vptpower.com





## 3.2 PERFORMANCE SPECIFICATIONS

Tcase = -55 °C to +125 °C, Vin = +28 V ± 5%, Full Load1, Unless Otherwise Specified

		SV	LTR280	5D	SI	LTR281	2D		
Parameter	Conditions	Min	Тур	Max	Min	Тур	Max	Units	
INPUT									
Voltage	Continuous	15	28	50	15	28	50	V	
	Transient, 1 sec <sup>4</sup>	-	-	80	-	-	Max	V	
Current	INH < 1.5 V	-	4	6	-	4	6	mA	
	No Load	-	60	90	-	75	Max           50           80           6           100           50           14.8           14.5           12.12           12.24           12.20           12.36           40           28           3.33           20           200           50           200           50           200           50           450           400           1200           500           20           50	mA	
Ripple Current	20 Hz to 10 MHz	-	30	50	-	30		mApp	
Undervoltage Lockout	Turn-On	12.0	13.6	14.8	12.0	13.6		V	
C	Turn-Off <sup>4</sup>	11.0	12.8	14.5	11.0	12.8	14.5	V	
OUTPUT STATIC	Turr-On							-	
Voltage	+Vout, Tcase = 25 °C	4.950	5	5.050	11.88	12	12 12	V	
Voltage	+Vout, Tcase = -55 °C to +125 °C	4.925	5	5.075	11.76	12		V	
	-Vout, Tcase = 25 °C	4.850	5	5.150	11.80	12		V	
	-Vout, Tcase = -55 °C to +125 °C	4.800	5	5.200	11.64	12		V	
Power <sup>2,6</sup>	Total	0	-	30	0	-		w	
Power-, o	Either Output	0		21	0			W	
2.6	<u> </u>							_	
Current <sup>2,6</sup>	Total	0	-	6.0	0	-		A	
D: 1 1/1	Either Output	0	-	4.2	0	-		A	
Ripple Voltage	20 Hz to 10 MHz	-	20	60	-	20		mVpp	
Line Regulation	+Vout, V <sub>IN</sub> = 16 V to 40 V	-	1	20	-	11		mV	
	-Vout, V <sub>IN</sub> = 16 V to 40 V	-	60	200	-	50		mV	
Load Regulation <sup>7</sup>	+Vout, No Load to Full Load	-	5	50	-	2		mV	
	-Vout, No Load to Full Load	-	50	200	-	30	200	mV	
Cross Regulation, –Vout	+Vout: 70% load, -Vout: 30% load		300	650	_	450	650	mV	
	+Vout: 30% load, -Vout: 70% load								
Load Fault Power Dissipation	Overload <sup>4</sup>	-	-	16	-	-	15	W	
	Short Circuit	-	-	16	-	-	15	W	
OUTPUT DYNAMIC									
Load Step, Half to Full Load, Either Output	Output Transient	-	150	400	-	300	450	mVpk	
	Recovery <sup>3</sup>	-	230	350	-	200	400	μs	
Line Step <sup>4</sup> , Vin = 16 V to 40 V	Output Transient	-	300	600	-	700	Max  50 80 6 100 50 14.8 14.5  12.12 12.24 12.20 12.36 40 28 3.33 2.33 50 20 200 650 15 15 450 400 1200 500 20 50 1.5 13.5 600  - 500 550 52 55 90 12.30 12.48	mVpk	
	Recovery <sup>3</sup>	_	350	500	_	300		μs	
Turn-On, Vin = 0 to 28 V	Delay	-	10	20	_	10		ms	
1 uiii-Oii, Viii – 0 to 26 V	Overshoot	<del>-</del>	0	25	-	0		<del>                                     </del>	
FUNCTION	Oversilloot	-	0	23	-	0	30	mVpk	
	Outroot look in to al			4.5	0		4.5	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	
INH Pin Input <sup>4</sup>	Output Inhibited	0	-	1.5	0	-		V	
INH Pin Open Circuit Voltage <sup>4</sup>	Output Enabled	9	12.5	13.5	9	12.5	13.5	V	
SYNC Frequency Range		500	-	600	500	-	600	kHz	
GENERAL								,	
Efficiency		74	78	-	78	83	-	%	
Capacitive Load <sup>4</sup>		-	-	500	-	-	500	μF	
Switching Frequency		450	525	550	450	525	550	kHz	
Isolation	500 V DC, Tcase = 25 °C	100	-	-	100	-	-	ΜΩ	
Weight	Non-flanged package option	-	-	52	-	-	52	g	
	Flanged package option	-	-	55	-	-	55	g	
MTBF (MIL-HDBK-217F)	Class H, SF @ Tcase = 55 °C	-	774	-	-	774	-	khr	
	Class K, SF @ Tcase = 55 °C	-	3.10		-	3.10		Mhr	
POST-RAD END-OF-LIFE LIMITS <sup>5</sup>									
Input Ripple Current		-	-	70	-	-	90	mApp	
Output Voltage	+Vout, Tcase = -55 °C to +125 °C	4.90	-	5.10	11.70	-		V	
	-Vout, Tcase = -55 °C to +125 °C	4.75	-	5.25	11.48	-	12.48	V	
Switching Frequency		435	-	575	435	-	575	kHz	

<sup>1.</sup> Half load at +Vout and half load at -Vout.

**Sales Information** Phone: (425) 353-3010 Fax: (425) 353-4030

Web: www.vptpower.com

E-mail: vptsales@vptpower.com

SVLTR2800D - 2.0

Up to 70% of the total power or current can be drawn from either of the two outputs.
 Time for output voltage to settle within 1% of steady-state value.
 Verified by initial electrical design verification. Post design verification, parameter shall be guaranteed to the limits specified.
 End-of-Life performance includes aging and radiation degradation and is within standard limits except where noted.

Derate linearly to 0 at 135 °C. 5% Load to Full Load at -55 °C.





# 3.2 PERFORMANCE SPECIFICATIONS (CONTINUED)

Tcase = -55 °C to +125 °C, Vin = +28 V ± 5%, Full Load1, Unless Otherwise Specified

		1	LTR281		
Parameter	Conditions	Min	Тур	Max	Units
INPUT					,
Voltage	Continuous	15	28	50	V
	Transient, 1 sec <sup>4</sup>	-	-	80	V
Current	INH < 1.5 V	-	4	6	mA
	No Load	-	75	100	mA
Ripple Current	20 Hz to 10 MHz	-	25	50	mAp
Undervoltage Lockout	Turn-On	12.0	13.6	14.8	V
	Turn-Off <sup>4</sup>	11.0	12.8	14.5	V
OUTPUT STATIC					
Voltage	+Vout, Tcase = 25 °C	14.85	15	15.15	V
	+Vout, Tcase = -55 °C to +125 °C	14.70	15	15.30	V
	-Vout, Tcase = 25 °C	14.80	15	15.20	V
	-Vout, Tcase = -55 °C to +125 °C	14.55	15	15.45	V
Power <sup>2,6</sup>	Total	0	-	40	W
	Either Output	0	-	28	W
Current <sup>2,6</sup>	Total	0	-	2.67	Α
	Either Output	0	-	1.87	Α
Ripple Voltage	20 Hz to 10 MHz	-	20		mVp
ine Regulation	+Vout, V <sub>IN</sub> = 16 V to 40 V	-	1	20	mV
3	-Vout, V <sub>IN</sub> = 16 V to 40 V	-	30	200	mV
_oad Regulation <sup>7</sup>	+Vout, No Load to Full Load	-	1	50	mV
Load Regulation	-Vout, No Load to Full Load	-	30		mV
Cross Regulation, –Vout	+Vout: 70% load, -Vout: 30% load			50 80 6 100 50 14.8 14.5 15.15 15.30 15.20 15.45 40 28 2.67 1.87 50 20	1111
Stood Rogalation, Voul	+Vout: 30% load, -Vout: 70% load		400	650	mV
_oad Fault Power Dissipation	Overload <sup>4</sup>	-	-	1/1	w
Load Fault Fower Dissipation	Short Circuit				W
OUTPUT DYNAMIC	Short Circuit	_	_	14	VV
Load Step, Half to Full Load, Either Output	Output Transient	-	300	500	mVp
toda Stop, Flan to Fan Esda, Eliner Sutput			150		<u> </u>
A	Recovery <sup>3</sup>	-			μs
ine Step <sup>4</sup> , Vin = 16 V to 40 V	Output Transient	-	800	1200	mVp
	Recovery <sup>3</sup>	-	300	500	μs
Γurn-On, Vin = 0 to 28 V	Delay	-	10	20	ms
	Overshoot	-	0	50	mVp
FUNCTION					
NH Pin Input <sup>4</sup>	Output Inhibited	0	-	1.5	V
NH Pin Open Circuit Voltage <sup>4</sup>	Output Enabled	9	12.5	13.5	V
SYNC Frequency Range		500			kHz
GENERAL					
Efficiency		79	84		%
Capacitive Load <sup>4</sup>				500	μF
Switching Frequency		450	525		kHz
solation	500 V DC, Tcase = 25 °C	100	J2J	-	MΩ
Veight	Non-flanged package option	-		52	g
Toight	Flanged package option	-	-		g
MTBF (MIL-HDBK-217F)	Class H, SF @ Tcase = 55 °C	-	774		khr
WIDI (WILTIDDIY-2171)	Class K, SF @ Tcase = 55 °C	-	3.10		Mhr
POST-RAD END-OF-LIFE LIMITS <sup>5</sup>	Jid35 11, OF W 10456 - 00 0	_	5.10		IVIIII
nput Ripple Current			-	an	mAp
	+Vout, Tcase = -55 °C to +125 °C	14.625	<u> </u>		V
	· v out. 1003600 O tO + 120 O	1 17.023	-	10.010	V
Output Voltage	-Vout, Tcase = -55 °C to +125 °C	14.475	-	15 525	V

<sup>1.</sup> Half load at +Vout and half load at -Vout.

**Sales Information** 

Phone:(425) 353-3010 Fax: (425) 353-4030 SVLTR2800D - 2.0 Page 4

Up to 60% of the total power or current can be drawn from either of the two outputs.
 Time for output voltage to settle within 1% of steady-state value.
 Verified by initial electrical design verification. Post design verification, parameter shall be guaranteed to the limits specified.


<sup>5.</sup> End-of-Life performance includes aging and radiation degradation and is within standard limits except where noted.

<sup>6.</sup> Derate linearly to 0 at 135 °C.7. 5% Load to Full Load at -55 °C.




## **4.0 PERFORMANCE CURVES**


## 4.1.1 SVLTR2805D Efficiency (Typical, 25 °C)




## 4.1.2 SVLTR2805D Cross-Regulation (Typical, 25 °C)




## 4.2.1 SVLTR2812D Efficiency (Typical, 25 °C)




#### 4.2.2 SVLTR2812D Cross-Regulation (Typical, 25 °C)



# 4.3.1 SVLTR2815D Efficiency (Typical, 25 °C)



## 4.3.2 SVLTR2815D Cross-Regulation (Typical, 25 °C)




SVLTR2800D - 2.0 **Sales Information** Phone:(425) 353-3010 Fax: (425) 353-4030 E-mail: vptsales@vptpower.com


Web: www.vptpower.com




## **5.0 MECHANICAL OUTLINES AND PINOUT**

## **Non-Flanged Package Option:**







- 1. Tolerances are ±0.005" unless otherwise stated
- Case temperature is measured on the center of the baseplate surface
- Materials: Case (Steel, gold over nickel plated); Cover (Kovar, nickel plated); Pin (Copper-cored alloy 52, gold over nickel plated); Pin Seals (Ceramic)

Pin Function	Pin Function	Pin Function	n Pin Function
1 VIN	4 OUTCOM	7 CASE	10 INCOM
2 INHIBIT	5 -VOUT	8 CASE	
3 +VOUT	6 CASE	9 SYNC	

**Sales Information** SVLTR2800D - 2.0 Phone:(425) 353-3010 Fax: (425) 353-4030


E-mail: vptsales@vptpower.com


Web: www.vptpower.com Page 6



# **5.0 MECHANICAL OUTLINES AND PINOUT (CONTINUED)**

## Flanged Package Option:





- 1. Tolerances are ±0.005" unless otherwise stated
- Case temperature is measured on the center of the baseplate surface
   Mounting holes are not threaded. Recommended fastener is 6-32
- 4. Materials: Case (Steel, gold over nickel plated); Cover (Kovar, nickel plated); Pin (Copper-cored alloy 52, gold over nickel plated); Pin Seals (Ceramic)

Pin	Function	Pin	Function	Pin	Function	Pin	Function
1	VIN	4	OUTCOM	7	CASE	10	INCOM
2	INHIBIT	5	-VOUT	8	CASE		
3	+VOUT	6	CASE	9	SYNC		

Phone:(425) 353-3010 Fax: (425) 353-4030 E-mail: vptsales@vptpower.com Web: www.vptpower.com Page 7





#### **6.0 TECHNICAL NOTES**



Please note that many of these functions are also demonstrated in detail on the VPT website in the form of technical video labs.

#### **6.1 GENERAL INFORMATION**

#### **6.1.1 Topology Description**

The SVLTR2800D Series is an isolated dual-output flyback converter. It provides a positive and negative output voltage with respect to the OUTCOM pin. Up to 70% of the total output power is available from either output. The internal voltage regulation loop actively regulates the positive output using VPT's proprietary magnetic feedback technology. The negative output is regulated by cross-regulation of the transformer windings. The negative output is well-regulated for balanced load conditions. For unbalanced load conditions, refer to the cross-regulation performance graphs in Section 4.2 for expected performance. For a balanced or near-balanced load condition, the converter will regulate down to zero load, and no minimum load is required. For an unbalanced load condition, with negative loads greater than 10%, a minimum load of 10% is recommended on the positive output.

#### **6.1.2 External Components**

The SVLTR2800D Series is designed to operate stand-alone in most applications. It does not require any external components for proper operation or to meet the datasheet specifications. Input and output L-C filters are provided internally for low ripple and noise. To further reduce output ripple and noise, a small ceramic capacitor, 1  $\mu$ F to 10  $\mu$ F, can be added at the output. Most application specific ripple requirements can be met with the addition of output capacitors alone. External output capacitance can be added up to the maximum listed in Section 3.2.

#### 6.1.3 Source Impedance

The impedance of the 28 V input source can interact with the DC-DC converter and can affect performance. High source impedance is often caused by a long input cable or components added in series with the input. Source resistance will cause a DC voltage drop as the converter draws DC input current. This voltage drop is simply the cable resistance multiplied by the input current at low line. The voltage drop and the actual voltage at the input to the converter will determine the minimum source voltage at which the converter will operate. A high source inductance can interact with the feedback control loop of the converter. VPT's EMI filters will usually isolate the source and eliminate this problem. In some cases, additional input capacitance will be needed to stabilize the system.

#### 6.1.4 Output Configurations


Since the converter is isolated, the outputs can be used as a traditional dual-output, with a positive and negative voltage referenced to OUTCOM, or as a single-ended output referenced to -VOUT or +VOUT. For example, the SVLTR2812D model can provide +12 V and -12 V in the traditional dual output configuration, or can provide +24 V referenced to -VOUT, or -24 V referenced to +VOUT in single-ended configuration. In the single-ended configuration, the OUTCOM pin will be at +12 V relative to -VOUT.

The outputs of multiple converters can be stacked in series to provide higher voltages. When outputs of multiple modules are stacked, they naturally share the load. For example, two SVLTR2812D converters can be stacked to provide a 48 V output at 80 W.

## **6.2 FUNCTION DESCRIPTIONS**

#### 6.2.1 On/Off Control (Inhibit)

The INHIBIT pin is a primary-side control pin referenced to INCOM. The INHIBIT pin must be driven using an open collector or open drain configuration. Pulling INHIBIT low disables the converter output, removes bias voltage from internal control circuitry, and puts the converter in a state of minimum input current draw. Leaving INHIBIT open enables the output, allowing the converter to operate normally. The pin must be pulled below 1.5 V to disable the output. An optional capacitor from INHIBIT to INCOM may be used to delay turn-on. The INHIBIT pin should be left open if not used.



**Sales Information** Phone: (425) 353-3010 Fax: (425) 353-4030 SVLTR2800D - 2.0

E-mail: vptsales@vptpower.com Web: www.vptpower.com



# **SVLTR2800D Series**

#### 6.2.2 Frequency Synchronization (SYNC)

The SVLTR2800D Series will free run at a switching frequency of approximately 500 kHz, which has been set for optimum converter performance. Frequency synchronization is not necessary unless required by system constraints. The SVLTR2800D Series provides a frequency synchronization input (SYNC) referenced to INCOM.

The SYNC pin can be driven by an external clock. The internal clock and internal power train will operate at the frequency applied to the SYNC pin. The SYNC pin should be driven with a TTL type 5 V square wave signal. The duty cycle of the square wave should be between 20% and 80%. The SYNC pin is internally capacitively-coupled and the internal load is equivalent to 220 pF. Proper layout and circuit techniques are necessary to prevent noise from being injected into this pin. Synchronized converters should be physically located close together and share a low impedance INCOM connection. The SYNC pin can be left open or connected to INCOM if not used.

#### **6.3 PROTECTION FEATURES**

#### 6.3.1 Input Undervoltage Lockout

The SVLTR2800D Series provides input undervoltage lockout protection. For input voltages below the turn-on voltage, the converter will remain off, drawing minimal current from the source. When the input voltage exceeds the turn-on voltage, the converter will start. The lockout circuit is designed to tolerate slow ramping input voltage waveforms. VPT's proprietary magnetic feedback technology provides bias voltage to all secondary control circuits and control amplifiers before the output starts, ensuring a well-controlled start up sequence.

#### 6.3.2 Output Soft Start

The SVLTR2800D Series utilizes an output soft-start function to ramp the output in a controlled manner, eliminating output voltage overshoot and limiting inrush current at turn on. A voltage-mode soft-start ensures the output waveform remains consistent regardless of changes in the load current. The output rise time is approximately 8 ms. The soft-start function is active whether the module is turned on with an application of input voltage or from release of the inhibit pin. Under normal conditions, current drawn from the source during turn on will not exceed the full load input current. The turn-on delay time is specified from the application of input voltage (or release of the inhibit pin) until the output reaches 90% of its final value.

#### **6.3.3 Output Overcurrent Protection**

The SVLTR2800D Series provides output overcurrent and output short circuit protection. During a load fault condition, a constant output current control circuit reduces the converter duty cycle to limit the total output current to approximately 125% its rated value. The current limit protection circuit limits the sum of output currents in both +Vout and –Vout. It does not distinguish if the current is on the positive or negative output. The converter will continue to provide constant current into any overload or short circuit condition. This feature allows the converter to start into any capacitive load. Recovery is automatic and immediate upon removal of the fault condition. Sustained short circuit or overload operation can cause excessive power dissipation. Care should be taken to control the operating temperature of the converter in this condition.

### **6.4 THERMAL CONSIDERATIONS**

The SVLTR2800D Series is rated for full power operation at 125 °C. Operation above 125 °C is allowed at reduced power. Specifically, the output power should be derated linearly from full power at 125 °C to half power at 130 °C and to zero power at 135 °C. The operating temperature of the converter is specified on the baseplate of the converter. The converter is designed to be conduction-cooled, with the baseplate mounted to a heat sink, chassis, PCB, or other thermal surface. The internal power dissipating components are mounted to the baseplate of the converter and all heat flow is through the baseplate and mounting flanges. The lid of the converter does not provide a good thermal path.

The hybrid DC-DC converter contains many semiconductor components. The maximum temperature rise from junction to case is 18 °C at full load.

**Sales Information** Phone: (425) 353-3010 Fax: (425) 353-4030 SVLTR2800D - 2.0

Web: www.vptpower.com

E-mail: vptsales@vptpower.com



# **SVLTR2800D Series**

## **6.5 RADIATION HARDNESS ASSURANCE**

VPT takes a conservative approach to radiation testing to ensure product performance in a space environment. VPT's DLA-approved Radiation Hardness Assurance (RHA) plan documents VPT's processes and procedures for guaranteeing the performance of VPT products under various environmental conditions in space including Total Ionizing Dose (TID) and Single-Event Effects (SEE). Additionally, Enhanced Low Dose-Rate Sensitivity (ELDRS) effects are considered for all bipolar ICs used in the hybrid. Hardness is guaranteed by a combination of both hybrid-level characterization and Radiation Lot Acceptance Testing (RLAT) of all sensitive semiconductor piece-parts used within the hybrid.

#### 6.5.1 Radiation Test and Performance Levels

Radiation Environment	t	Piece Part RLAT	Hybrid-Level Characterization
Total Ionizing Dose	High Dose Rate (HDR)	60 krad(Si)	60 krad(Si)
(TID)	Low Dose Rate (LDR)	<sup>1</sup> 60 krad(Si)	60 krad(Si)
Single-Event Effects	Destructive (SEB, SEGR, SEL)	Not applicable	≥ 85 MeV/mg/cm²
(SEE)	Non-Destructive (SET, SEU)	Not applicable	≥ 85 MeV/mg/cm²

<sup>1.</sup> Piece-part LDR screening performed only on potentially ELDRS parts (bipolar ICs).

#### 6.5.2 RHA Plan Summary

Test	RHA Plan for SVL Series Isolated DC-DC Converters
Total Ionizing Dose (TID):	Sensitive semiconductor components undergo RLAT to 60 krad(Si) per MIL-STD-883 Method 1019. Converters are characterized to 60 krad(Si).
Enhanced Low Dose Rate Sensitivity (ELDRS):	All bipolar linear ICs are characterized for ELDRS and tested in accordance with MIL-STD-883 test method 1019 section 3.13
Single Event Effects (SEE):	Converters are characterized to LET ≥ 85 MeV/mg/cm² for both catastrophic events (SEL, SEB, SEGR) and functional interrupts (SEFI) under heavy ion exposure. Converters are also characterized for cross-section and magnitude of output transients (SET) for at least 3 different LET levels.
Radiation Lot Acceptance Testing (RLAT):	All production lots of sensitive semiconductor components undergo RLAT for TID at HDR and/or LDR as appropriate per part type.

#### 6.5.3 RHA Designators available on SMD

The SVLTR2800D series converters are available on SMD with RHA level L. See section 8.0 for full SMD number information.

#### 6.5.4 Supporting Documentation Available (Contact Sales)

Radiation Hardness Assurance Plan: DLA-approved RHA plan covering TID, SEE, and ELDRS

Worst-Case Analysis Report: Detailed worst-case analysis including electrical stress/derating limits and

guaranteed circuit performance post-radiation and end of life

Radiation Test Summary Report: Overview of piece-part RLAT and hybrid characterization for all guaranteed

environments. Also includes SEE cross-section data.

Reliability Report:
 MTBF report based on MIL-HDBK-217 reliability calculations.

Thermal Analysis Report: Component temperature rise analysis and measurement results.

**Sales Information** Phone: (425) 353-3010 Fax: (425) 353-4030 SVLTR2800D - 2.0

Web: www.vptpower.com

E-mail: vptsales@vptpower.com





## 7.0 ENVIRONMENTAL SCREENING

100% tested per MIL-STD-883 as referenced to MIL-PRF-38534.

Contact sales for more information concerning additional environmental screening and testing options. VPT Inc. reserves the right to ship higher screened or SMD products to meet orders for lower screening levels at our sole discretion unless specifically forbidden by customer contract.

Test	MIL-STD-883 Test Method, Condition	/H+ (Class H + PIND)	/K (Class K)	/EM (Engineering Model) Non-QML <sup>1,6</sup>
Non-Destructive Bond Pull	TM2023	•2	•	<b>_</b> 2
Internal Visual	TM2010, TM2017, TM2032 (MIL-STD-750, TM2072, TM2073)	•	•	•
Temperature Cycling	TM1010, Condition C -65 °C to 150 °C, Ambient	•	•	
Constant Acceleration	TM2001, 3000g, Y1 Direction	•	•	
PIND <sup>3</sup>	TM2020, Condition A	•2	•	
Pre Burn-In Electrical	25 °C		•	
	TM1015, 320 hrs., 125 °C, Case Typ		•	
Burn-In	TM1015, 160 hrs., 125 °C, Case Typ	•		
	24 hrs., 125 °C, Case Typ			•
F: 151 .: 1	MIL-PRF-38534, Group A Subgroups 1-6 -55 °C, 25 °C, 125 °C <sup>4</sup>	•	•	
Final Electrical	MIL-PRF-38534, Group A Subgroups 1 and 4 25 °C			•
	TM1014, Fine Leak, Condition A2 or B1	•	•	
Hermeticity (Seal)	TM1014, Gross Leak, Condition C1 or B2	•	•	
	Gross Leak, Dip (1x10 <sup>-3</sup> )			•
Radiography <sup>5</sup>	TM2012		•	
External Visual	TM2009	•	•	•

<sup>1.</sup> Non-QML products may not meet all requirements of MIL-PRF-38534

 Sales Information
 Phone: (425) 353-3010
 Fax: (425) 353-4030
 SVLTR2800D - 2.0

 E-mail: <a href="mailto:vptsales@vptpower.com">vptsales@vptpower.com</a></a>
 Web: <a href="mailto:www.vptpower.com">www.vptpower.com</a>
 Page 11

Not required per MIL-PRF-38534. Test performed for additional product quality assurance

<sup>3.</sup> PIND test Certificate of Compliance included in product shipment

<sup>4. 100%</sup> R&R testing with all test data included in product shipment

Radiographic test Certificate of Compliance and film(s) or data CD included in product shipment

Engineering models utilize only the screening specified and are not considered compliant for flight use



# 8.0 STANDARD MICROCIRCUIT DRAWING (SMD) NUMBERS

Standard Microcircuit Drawing Number	SVLTR2800D Series Similar Part Number
5962L1621501HXC	SVLTR2805D/H+
5962L1621501HXA	SVLTR2805D/H+-E
5962L1621501HYC	SVLTR2805DF/H+
5962L1621501HYA	SVLTR2805DF/H+-E
5962L1621501KXC	SVLTR2805D/K
5962L1621501KXA	SVLTR2805D/K-E
5962L1621501KYC	SVLTR2805DF/K
5962L1621501KYA	SVLTR2805DF/K-E
5962L1621502HXC	SVLTR2812D/H+
5962L1621502HXA	SVLTR2812D/H+-E
5962L1621502HYC	SVLTR2812DF/H+
5962L1621502HYA	SVLTR2812DF/H+-E
5962L1621502KXC	SVLTR2812D/K
5962L1621502KXA	SVLTR2812D/K-E
5962L1621502KYC	SVLTR2812DF/K
5962L1621502KYA	SVLTR2812DF/K-E
5962L1621503HXC	SVLTR2815D/H+
5962L1621503HXA	SVLTR2815D/H+-E
5962L1621503HYC	SVLTR2815DF/H+
5962L1621503HYA	SVLTR2815DF/H+-E
5962L1621503KXC	SVLTR2815D/K
5962L1621503KXA	SVLTR2815D/K-E
5962L1621503KYC	SVLTR2815DF/K
5962L1621503KYA	SVLTR2815DF/K-E

Do not use the SVLTR2800D Series similar part number for SMD product acquisition. It is listed for reference only. For exact specifications for the SMD product, refer to the SMD drawing. SMDs can be downloaded from the DLA Land and Maritime (Previously known as DSCC) website at <a href="https://landandmaritimeapps.dla.mil/programs/defaultapps.asp">https://landandmaritimeapps.dla.mil/programs/defaultapps.asp</a>. The SMD number listed above represents the Federal Stock Class, Device Type, Device Class Designator, Case Outline, Lead Finish and RHA Designator (where applicable). Please reference the SMD for other screening levels, lead finishes, and radiation levels. All SMD products are marked with a "Q" on the cover as specified by the QML certification mark requirement of MIL-PRF-38534.

**Sales Information** Phone: (425) 353-3010 Fax: (425) 353-4030 SVLTR2800D - 2.0 Web: www.vptpower.com Page 12





## 9.0 ORDERING INFORMATION

S	VLTR	28	05	D	F	/K	-	XXX
	1	2	3	4	5	6		7

(1) Product Series	(2) Nominal Input Voltage	(3) Output Voltage	(4) Number of Outputs	(5) Package Option	(6) Screening Code <sup>1,2,3</sup>	(7) Additional Screening Code
SVLTR	<b>28</b> 28 V	<b>05</b> 5 V <b>12</b> 12 V <b>15</b> 15 V	<b>D</b> Dual	(None) Non-Flanged <b>F</b> Flanged	/EM Engineering Model /H+ Class H + PIND /K Class K	Contact Sales

- Contact the VPT Sales Department for availability of Class H (/H) or Class K (/K) qualified products
- VPT Inc. reserves the right to ship higher screened or SMD products to meet lower screened orders at our sole discretion unless specifically forbidden by customer
- Engineering models utilize only the standard screening specified and are not considered compliant for flight use. These models are intended for low volume engineering characterization only and have no guarantee regarding operation in a radiation environment. The customer must place the following statement on each line item of their purchase order(s) for /EM units when ordering engineering models:

"(Customer Name) acknowledges that the /EM unit listed in this line item is not permitted for flight use and will be used for Engineering characterization only."

Please contact your sales representative or the VPT Inc. Sales Department for more information concerning additional environmental screening and testing, different input voltage, output voltage, power requirements, source inspection, and/or special element evaluation for space or other higher quality applications.

**Sales Information** Phone:(425) 353-3010 Fax: (425) 353-4030 Web: www.vptpower.com Page 13



## **10.0 CONTACT INFORMATION**

To request a quotation or place orders please contact your sales representative or the VPT, Inc. Sales Department at:

**Phone**: (425) 353-3010 **Fax**: (425) 353-4030

**E-mail**: vptsales@vptpower.com

All information contained in this datasheet is believed to be accurate, however, no responsibility is assumed for possible errors or omissions. The products or specifications contained herein are subject to change without notice.

## 11.0 ADDITIONAL INFORMATION

Visit the VPT website for additional technical resources, including:

## **Product Catalogs**



**Technical Video Labs** 



## **Application Notes and White Papers**



Additional Products For <u>Avionics/Military</u>, <u>Hi-Rel COTS</u>, and <u>Space Applications</u>



**Sales Information** Phone: (425) 353-3010 Fax: (425) 353-4030 SVLTR2800D - 2.0

Web: www.vptpower.com

E-mail: vptsales@vptpower.com